

PARTS LIST

UNITS	REF.	DESCRIPTION
600'	#1	1/4" GAC Cable
(6)	#2	TB-12 Turnbuckles (for horizontal and pull-back cables)
(4)	#3	TB-6 Turnbuckles (for vertical cables)
(6)	#4	1/2" x 12" Long Eyebolts
(40)	#5	1/4" Cable Clamps
(400)	#6	8 mm Carabiner Clips

Recommended Pole Size: (Poles not included)
10.75" OD x 0.375" Wall

Recommended Netting:
High-Impact 1-3/4" Sq Mesh
Rope Bound Netting

NOTE: (IF INSTALLING WITH A WALL)
- Eyebolts are recommended every 3' - 4'
on top of wall to anchor bottom cable
- Wall and hardware/eyebolts for wall are
not included



